Specification #5315, Reference 999 SS PRT RAM HEMI

Customer	Stock Vacuum	Job #	**4409**
Reference	999 SS PRT RAM HEMI	Date	16-Mar-2021

ITEM	DESCRIPTION	QTY
CHASSIS-FLOWMARK SUPPLIED	**Chassis** - 2019 RAM 5500-3AH, 84in CA, HEMI, see specs	1

PR-SS-999-KCT	**Stainless 999 Gallon Portable Restroom Unit, Including:**
	  - 999 USG stainless construction restroom tank
	    - 699 gallons waste
	    - 300 gallons fresh
	    - Low work station for driver convenience
	    - Manway/primary combo
	    - 2 inlets with risers and deflectors
	    - 3" discharge
	    - 4" top water fill, 2" top water vent
	    - (2) 30x30 storage cabinets with shelf
	    - Dry Deck tile in cabinet bottoms
	    - (4) LED work lights
	  - 210cfm NVE304 gearbox drive vacuum pump system
	    - Secondary shut off and final filter
	    - Vacuum and pressure relief valves
	    - pump flush kit
	  ~~- FloJet 12volt wash down system with 50' garden hose and nozzle~~
	  ~~- In-cab pump and worklight controls~~
	  ~~- Single service~~
	    ~~- Single 30' 2" vacuum inlet hose with valve and wand assembly~~
	      ~~- Single 2" bucket fill~~
	    - Single 5 gallon bucket holder
	  - 3" discharge with full port valve, adapter and dust cap
	  - 2 unit, fold up toilet hauler
	    - S/T/T lights, DOT triple lights in deck, fold down license plate
	    - 2" light-duty hitch and wiring adapter
	  - Mounted on FlowMark supplied cab & chassis
	  - 7-year no-leak tank warranty
		1

PR-OPT-KCT-DSS	**Dual Service, Standard Tanks**
	  - Add 30' x 2" vacuum hose with wand and stinger to curb side
	  - Add bucket fill to curb side
		1

PR-OPT-KCT-DC10	**DC10 Pump Upgrade**
	  - Install DC10 water pump in place of FloJet
	  - Includes 17 minute timer, wiring, install
	  - Includes exernal remote panel in place of in-cab controls f or operation of PTO, water pump and work lights
		1

PR-OPT-KCT-HANNAY	**Hannay Reel**
	  - Install Hannay spring rewind reel assembly in place of garden hose
	  - Includes 50' hose, nozzle, install
		1